



NOTES:

- 1) DEVELOPER SHALL INSTALL AN APPROVED DOUBLE CHECK DETECTOR CHECK ASSEMBLY.
- 2) ASSEMBLY MUST BE ACCESSIBLE FOR TESTING AND MAINTENANCE.
- 3) ON APPROVAL OF S.C.W.C, DOUBLE CHECK VALVE ASSEMBLY MAY BE INSTALLED IN AN ADEQUATELY SIZED VAULT. INSTALL METER READING LID PER STANDARD DRAWING No.21 CENTERED OVER BY-PASS METER. METER MUST BE WITHIN 12" OF TOP OF VAULT.
- 4) ALL NEWLY INSTALLED BACKFLOW PREVENTION ASSEMBLIES MUST BE TESTED IN ACCORDANCE WITH LOCAL ORDINANCE PRIOR TO BEING PUT IN SERVICE.
- 5) METER SHALL BE INCLUDED WITH DEVICE AND READ IN CUBIC FEET.

SOUTHERN CALIFORNIA WATER COMPANY

DRAWN BY: JEFF BERG DATE: 8/96

REVISED: _____

DOUBLE CHECK DETECTOR CHECK ASSEMBLY

STANDARD DRAWING NO. 6.6