



NOTES:

- 1) DEVELOPER SHALL INSTALL AN APPROVED REDUCED PRESSURE PRINCIPLE DETECTOR CHECK ASSEMBLY.
- 2) ASSEMBLY MUST BE ACCESSIBLE FOR TESTING AND MAINTENANCE.
- 3) ALL NEWLY INSTALLED ASSEMBLIES MUST BE TESTED IN ACCORDANCE WITH LOCAL ORDINANCE PRIOR TO BEING PUT IN SERVICE.
- 4) METER SHALL BE INCLUDED WITH DEVICE AND READ IN CUBIC FEET.

SOUTHERN CALIFORNIA WATER COMPANY

DRAWN BY: JEFF BERG DATE: 8/96

REVISED: _____

REDUCED PRESSURE PRINCIPLE
DETECTOR CHECK ASSEMBLY

STANDARD DRAWING NO. 6.7